

**CITY OF MOUNT HOPE
FAYETTE COUNTY, WEST VIRGINIA**

CONTRACT NO. 1 – LIFT STATION AND FORCEMAIN IMPROVEMENTS

ADDENDUM NO. 3

MARCH 6, 2019

To whom it may concern:

A. BOILER PLATE

1. N/A

B. SPECIFICATIONS

1. N/A

C. DRAWINGS

1. N/A

D. QUESTIONS AND CLARIFICATIONS

The following are clarifications regarding the above referenced project.

1. The 200 LF of Exposed DIP Tank Drain Line, shown on Drawing Sheets 4 and 4A, shall be Long Span, Flanged DIP and the Center to Center Spacing of the Concrete Pier Supports shall be 27 feet.
2. The 36" x 93" Aluminum Dual Door Access Hatch over the pumps, shown on Drawing Sheets PS3, PS4, and PS6 shall be replaced with three (3) 30" x 30" Aluminum Access Hatches.

E. GENERAL

1. Bidders are hereby notified to acknowledge receipt of all addenda in space provided on the Bid Form.

If you have any questions or need any other information please do not hesitate to contact me.

Sincerely,

THE THRASHER GROUP, INC.



JEFFERY D. EKSTROM, PE.
Project Manager

