

**GREATER HARRISON COUNTY PUBLIC SERVICE DISTRICT  
HARRISON COUNTY, WEST VIRGINIA  
CONTRACT #3 – ROUTE 73 SANITARY SEWER EXTENSION**

**THRASHER PROJECT # 101-020-0846**

ADVERTISEMENT FOR BIDS

Sealed Bids for the construction of the Contract #3 – Route 73 Sanitary Sewer Extension will be received, by the Greater Harrison County PSD at the West Milford Community Center located at 925 Liberty Street, West Milford, Harrison County, West Virginia until 2:00 PM local time on Thursday, May 30, 2019 at which time the Bids received will be publicly opened and read.

The approximate quantities of work to be bid upon are described as follows:

1 LS Mobilization/demobilization, 1 LS sediment and erosion control measures, 220 LF 12" Ductile Iron CL-50 Gravity Sewer (0'-6' Deep), 235 LF 12" Ductile Iron CL-50 Gravity Sewer (6'-9' Deep), 270 LF 12" Ductile Iron CL-50 Gravity Sewer (9'-12' Deep), 1,650 LF 12" Ductile Iron CL-50 Gravity Sewer (12'-15' Deep), 35 LF 12" Ductile Iron CL-50 Gravity Sewer (15'-18' Deep), 35 LF 12" PVC SDR-35 Gravity Sewer (0'-6' Deep), 955 LF 12" PVC SDR-35 Gravity Sewer (6'-9' Deep), 1,180 LF 12" PVC SDR-35 Gravity Sewer (9'-12' Deep), 1,300 LF 12" PVC SDR-35 Gravity Sewer (12'-15' Deep), 35 LF 12" PVC SDR-35 Gravity Sewer (15'-18' Deep), 1,340 LF 8" Ductile Iron CL-50 Gravity Sewer (0'-6' Deep), 1,860 LF 8" Ductile Iron CL-50 Gravity Sewer (6'-9' Deep), 570 LF 8" Ductile Iron CL-50 Gravity Sewer (9'-12' Deep), 650 LF 8" Ductile Iron CL-50 Gravity Sewer (12'-15' Deep), 105 LF 8" Ductile Iron CL-50 Gravity Sewer (15'-18' Deep), 7,800 LF 8" PVC SDR-35 Gravity Sewer (0'-6' Deep), 13,100 LF 8" PVC SDR-35 Gravity Sewer (6'-9' Deep), 3,660 LF 8" PVC SDR-35 Gravity Sewer (9'-12' Deep), 900 LF 8" PVC SDR-35 Gravity Sewer (12'-15' Deep), 910 LF 6" Ductile Iron CL-50 Gravity Sewer (0'-6' Deep), 370 LF 6" Ductile Iron CL-50 Gravity Sewer (6'-9' Deep), 25 LF 6" Ductile Iron CL-50 Gravity Sewer (9'-12' Deep), 5,100 LF 6" PVC SDR-35 Gravity Sewer (0'-6' Deep), 6,700 LF 6" PVC SDR-35 Gravity Sewer (6'-9' Deep), 190 LF 6" PVC SDR-35 Gravity Sewer (9'-12' Deep), 35 LF 6" PVC SDR-35 Gravity Sewer (12'-15' Deep), 730 LF 4" & 8" PVC C-900 DR-18 Forcemain In Same Trench, 5,570 LF 4" & 8" PVC C-900 DR-18 Forcemain Installed with 8" Gravity, 580 LF 8" PVC C-900 DR-18 Forcemain Installed with 8" Gravity, 470 LF 4" PVC C-900 DR-18 Forcemain Installed with 8" Gravity, 730 LF 4" PVC SDR-18 Forcemain, 360 LF 6" PVC SDR-35 Service Lateral Pipe, 520 LF 4" Ductile Iron CL-50 Service Lateral Pipe, 5,340 LF 4" PVC SDR-35 Service Lateral Pipe, 7 EA Concrete Anchor, 1 EA Straddle Manhole, 3 EA Flume Manhole, 295 EA Manhole Base, Cone Top & Watertight Casting and Lid (0' - 6' Deep), 775 VF 48" Diameter Manhole Riser Pipe, 20 EA Manhole Drop Connection (2'-6'), 10 EA Manhole Drop Connection (6' - Up), 1 EA 12" x 4" Ductile Iron Wye Service Connection, 1 EA 12" x 4" Wye Service Connection, 3 EA 8" x 6" Wye Service Connection, 18 EA 8" x 4" Ductile Iron Wye Service Connection, 118 EA 8" x 4" Wye Service Connection, 3 EA 6" x 6" Wye Service Connection, 11 EA 6" x 4" Ductile Iron Wye Service Connection, 88 LF 6" x 4" Wye Service Connection, 3 EA 6" Customer Cleanout, 228 EA 4" Customer Cleanout, 6 EA 8" Terminal Gravity Cleanout, 48 EA 6" Terminal Gravity Cleanout, 5 EA 4" Terminal Gravity Cleanout, 95 LF 36" Steel Casing (Bore and Jack), 160 LF 24" Steel Casing (Bore and Jack), 480

LF 16" Steel Casing (Bore and Jack), 140 LF 16" Steel Casing (Open Cut), 440 LF 12" Steel Casing (Bore and Jack), 105 LF 12" Steel Casing (Open Cut), 5 EA 8" Pressure In-Line Cleanout, 8 EA 4" Pressure In-Line Cleanout, 3 EA 8" Air/Vacuum Release Valve, 7 EA 4" Air/Vacuum Release Valve, 1 EA Cut and Plug Existing 12" PVC Sewer Line, 1,900 LF Stream Bank Slope Protection, 390 LF Mulch Netting, 150 LF Rip Rap Ditch, 35 LF Ditch Repair (Concrete), 3,300 LF Road Repair (Gravel), 170 LF Road Repair (Concrete), 230 LF Road Repair (HMA), 780 LF Driveway Repair (Gravel), 250 LF Driveway Repair (Concrete), 150 LF Driveway Repair (HMA), 150 LF Road Repair (HMA) w/ 1½" HMA Overlay, 70 LF Type "A" Trench Repair with 1½" HMA Overlay, 2,700 LF Type "B" Trench Repair with 1½" HMA Overlay, 1,950 LF Type "B" Trench Repair, 45,000 LF Restoration, 1 LS Concrete Effluent Headwall w/ Outfall Sign, 1 LS Pump Station #45 (Woodcrest Acres), 1 LS Pump Station #46.

The Work will be substantially completed within 270 calendar days after the date when the Contract Times commence to run, and completed and ready for final payment within 300 days after the date when the Contract Times commence to run. Liquidated damages shall be \$1,200.00 per day.

The Issuing Office for the Bidding Documents is: The Thrasher Group, Inc., 600 White Oaks Blvd., Bridgeport, WV 26330. Prospective Bidders may examine the Bidding Documents at the Issuing Office on Mondays through Fridays between the hours of 8:00 am to 5:00 pm, and may obtain copies of the Bidding Documents from the Issuing Office as described below.

Complete sets of Bidding Documents may be obtained from the office of Thrasher, 600 White Oaks Boulevard, P. O. Box 940, Bridgeport, WV 26330, for the following costs:

- Bidding Documents issued as hard copy drawings and hard copy specifications are available for \$150.00 per set.
- Bidding Documents issued as hard copy drawings and digital Specifications on a C.D., are available for \$75.00 per set.
- Bidding Documents issued as digital drawings and digital specifications on a C.D., are available for \$50.00 per set.

Amounts paid are not subject to refund.

Partial sets of Bidding Documents will not be available from the Issuing Office. Neither Owner nor Engineer will be responsible for full or partial sets of Bidding Documents, including Addenda if any, obtained from sources other than the Issuing Office.

Bidding Documents also may be examined at

Greater Harrison County PSD  
151 Peninsula Park Avenue  
West Milford, WV 26451

The Thrasher Group, Inc.  
600 White Oaks Boulevard  
Bridgeport, WV 26330

Contractor's Association of WV  
2114 Kanawha Boulevard East  
Charleston, WV 25311

A two envelope system will be used.

Envelope No. 1 must have the following information presented on the front:

Name and address of Bidder  
Bid on Contract #3 - Route 73 Sanitary Sewer Extension  
Received by the Greater Harrison County Public Service District

Envelope No. 2 labeled “Bid Proposal” shall also be placed inside of Envelope #1.

Envelope No. 1 will be opened first and the Bid Opening Requirement items checked for compliance as outlined on the Bid Opening Checklist on page BOR - 1 of these contract documents. If such documents are found to be in order, Envelope No. 2 “Bid Proposal”, will then be opened and will be publicly read aloud. If the documents required to be contained in Envelope No. 1 are not in order, Envelope No. 2 “Bid Proposal” will not be opened and the Bid will be considered non-responsive and will be returned to the Bidder.

A bidder may not withdraw his bid for a period of ninety (90) days after the date set for the opening of bids.

Bids shall be accompanied by a certified check or bid bond payable to Greater Harrison Public Service District in an amount equal to five percent (5%) of the base bid.

Nondiscrimination in Employment - Bidders on this work will be required to comply with the President's Executive Order Number 11246 and the provisions of Executive Order No. 10925 as included therein. The requirements for bidders and contractors under this order are explained in the specifications.

Suspension and Debarment – Recipient shall not entertain the use of businesses that are listed on the “System for Award Management” (SAM) at [www.Sam.gov](http://www.Sam.gov) in accordance with 2 CFR Part 1532 and Subpart B and C of 2 CFR Part 180.

Prospective Bidders should note that this Contract will include the following critical requirements as identified in the Contract Documents.

1. Affirmative Action Program Requirements and Goals
2. Certificate of Non-Segregated Facilities
3. Specific Labor Standard Provisions

American Iron and Steel Requirement – P.L. 113-76 Consolidated Appropriations Act, 2014 (ACT), includes an “American Iron and Steel” (AIS) requirement in section 436 that requires Clean Water State Revolving Loan Fund (CWSRF) and Drinking Water Revolving Loan Fund (DWSRF) assistance recipients to use iron and steel products that are produced in the United States for projects for the construction, alteration, maintenance, or repair of a public water system or treatment works.

Notice of Federal Wage Requirements – Contractors are required to comply with all laws pertaining to prevailing wage rates for the federal wages rates issued in accordance with the Davis Bacon Act.

Contractor is required to provide the Drug Free Workplace Certification in accordance with WV Code 21-1D-5.

All Bidders are required to have a West Virginia Contractor's License per Section §21-11-11 of the West Virginia Code.

Bids received after the scheduled closing time for the reception of bids will be returned unopened to the bidders.

The Greater Harrison County PSD reserves the right to reject any and all bids.

A **MANDATORY** pre-bid conference will be held at 10:00 AM local time on Thursday, May 9, 2019 at the **Greater Harrison County PSD, at the West Milford Community Center located at 925 Liberty Street, West Milford, Harrison County, West Virginia.**

JAMES SCUDERE, CHAIRMAN  
GREATER HARRISON COUNTY PUBLIC SERVICE DISTRICT

The Thrasher Group, Inc.  
600 White Oaks Boulevard  
Bridgeport, WV 26330

END OF ADVERTISEMENT FOR BIDS