


CITY OF WINFIELD  
 PUTNAM COUNTY, WEST VIRGINIA  
 FOR  
 CONTRACT NO. 1 - WASTEWATER TREATMENT PLANT IMPROVEMENTS  
 BID TABULATION  
 BID OPENING: Tuesday, February 11, 2020, 2:00 PM

Item	Qty.	Description	Hayslett Construction Company Inc. #WV000205		Orders Construction Company Inc. #WV000007		Mid Atlantic Construction Inc. #WV005529		Breckenridge Corporation #WV001651		Triton Construction Inc. #WV046687	
			\$	\$	\$	\$	\$	\$	\$	\$	\$	\$
1	1	LS Mobilization/Demobilization	\$ 70,000.00	\$ 70,000.00	\$ 35,000.00	\$ 35,000.00	\$ 42,500.00	\$ 42,500.00	\$ 198,000.00	\$ 198,000.00	\$ 237,000.00	\$ 237,000.00
2	1	LS To provide all labor, equipment, materials, and services to furnish and install the proposed new Wastewater Treatment Plant includes construction of a new headworks which consists of one (1) center flow mechanical fine screen with screenings processing, one (1) manual bar screen, vortex grit removal system with classifier, with all associated piping and appurtenances; construction of two (2) sequencing batch reactors (SBRs), one (1) post-equalization (EQ), one (1) aerobic digester, installation of all associated equipment, electrical and controls, and all other necessary appurtenances; new operations building which consists of kitchen, laboratory, locker room and bathroom, garage bays, belt filter press, polymer feed system, lime feed system and all associated equipment and controls, utility room and electrical room to house all electrical controls and SCADA equipment; construction of a new UV disinfection building to house all necessary UV disinfection equipment, a new non-potable pumping station with hydropneumatic tank and all other necessary appurtenances; emergency standby generator with automatic transfer switch; and decommissioning of existing wastewater treatment plant. The work shall include the installation of SBR equipment provided as part of Contract #2. Site work shall include paving, grading, piping, sidewalks, fencing, bollards, and all other work related items. The work shall include all ancillary mechanical, electrical, instrumentation and controls, erosion and sediment controls, SCADA, spare parts and accessories, civil, structural, architectural, and other items needed to provide a complete fully tested and operable system.	\$ 6,074,000.00	\$ 6,074,000.00	\$ 6,640,000.00	\$ 6,640,000.00	\$ 6,949,686.00	\$ 6,949,686.00	\$ 6,380,000.00	\$ 6,380,000.00	\$ 7,347,050.00	\$ 7,347,050.00
3	1	LS To provide all labor, equipment, materials, and services to provide capital improvements required by the electric company to provide adequate electrical service to the project site including additional power poles, transformers, meters, cable and/or conduit and other electrical accessories for the allowance amount.	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00	\$ 20,000.00
4	1	LS To procure, deliver and install office furniture in the newly constructed Administrative Building as authorized by the Owner and Engineer for the allowance amount.	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00	\$ 15,000.00
5	1	LS Winfield Way Lift Station Rehabilitation, Complete	\$ 117,000.00	\$ 117,000.00	\$ 163,000.00	\$ 163,000.00	\$ 177,314.00	\$ 177,314.00	\$ 110,000.00	\$ 110,000.00	\$ 213,000.00	\$ 213,000.00
6	350	DT Removal and Disposal of Sludge	\$ 80.00	\$ 28,000.00	\$ 914.00	\$ 319,900.00	\$ 630.00	\$ 220,500.00	\$ 2,100.00	\$ 735,000.00	\$ 235.00	\$ 82,250.00
<b>TOTAL BID</b>				\$ <b>6,324,000.00</b>		\$ <b>7,192,900.00</b>		\$ <b>7,425,000.00</b>		\$ <b>7,458,000.00</b>		\$ <b>7,914,300.00</b>

**THRASHER**

300 Association Drive  
 Charleston, WV 25311  
 Phone: 304-343-7601  
 Fax: 304-343-7604



Prepared By: Corey Smith, P.E. 02/12/2020