

**PRESTON COUNTY SEWER PUBLIC SERVICE DISTRICT
PRESTON COUNTY, WEST VIRGINIA**

**BRUCETON MILLS WASTEWATER TREATMENT PLANT
AND
VALLEY POINT LAGOON CLOSURE**

ADDENDUM # 4

JANUARY 19, 2021

**WVDEP SRF NO. C-544538
WVIJDC NO. 2015S-1614
THRASHER PROJECT NO. 101-020-1189**

TO WHOM IT MAY CONCERN:

This Addendum #4 provides two (2) requirements regarding the use of precast, post-tensioned concrete for the wastewater treatment plant.

Please acknowledge receipt of all Addenda in the Bid Opening Requirements and in the Bid Form.

A. GENERAL

1. The precast post-tensioned tank water-holding walls shall be a minimum of 12 inches thick.
2. The precast walls for the ICEAS basins shall be produced using a self-consolidating concrete mix with a maximum water to cement ratio of .38. All precast concrete shall be 5000 PSI at 28 days. The mix design shall be submitted to the Engineer for review.

Thank you for your interest in this project.

Sincerely,

THE THRASHER GROUP, INC.

STEVEN V. BUCHANAN, PE, PS



1/19/2021