



COMPLEX PROJECTS
REQUIRE RESOLVE
THRASHER'S GOT IT

**VILLAGE OF CALDWELL
NOBLE COUNTY, OHIO**

AREA E, AREA G, & INTERCEPTOR IMPROVEMENTS

ADDENDUM #2

FEBRUARY 21, 2023

THRASHER PROJECT #101-020-10020

TO WHOM IT MAY CONCERN:

The following are clarifications and responses to questions posed by contractors for the above-referenced project.

A. QUESTIONS AND RESPONSES

QUESTION 1

Does the Village or Thrasher have any flow rate data for the existing sanitary lines that are to be CIPP lined?

RESPONSE

No, we do not have any flow rate data.

QUESTION 2

Pertaining to the proposed 379 LF of 8" storm pipe shown on Belford St, sheet 35; is this run of pipe supposed to be 12" SLCPP? If not, will a pay item be added for the 8" SLCPP?

RESPONSE

This section is already accounted for in bid item #16, 611 12" Conduit, Type B. We have made this change on the attached. **REPLACE SHEET 35** with the attached.

QUESTION 3

In Addendum 1, bid item #51 Remove & Replace Brick Pavers as Per Plan was added. Please provide clarification for the pay terms between bid item #26 Pavement Repairs Misc: Remove & Replace and bid item #51.

RESPONSE

Pay item #51 is specific to the brick street repair. Pay item #26 is specific to the asphalt street repair.

QUESTION 4

Was a Geotech. report completed for this project?

RESPONSE

No Geotech. was performed as part of this project.

QUESTION 5

Is the CAD file available for the contractors to utilize for takeoffs?

RESPONSE

The CAD files will be made available to the successful bidder.

QUESTION 6

Does the Village require any additional fees/permits/licenses to perform the work for the project?

RESPONSE

We are not aware of any additional fees, licenses, or permits that are needed to be purchased by the contractor.

QUESTION 7

Related to the field QC & compaction testing for the trench backfill operations – will the owner or contractor be responsible for cover the costs of the compaction testing?

RESPONSE

The testing will be performed by a Thrasher Resident Project Representative on site. There shouldn't be any additional testing.

QUESTION 8

Are any other sanitary sewer lines required to be cleaned or videoed beyond the lines designated to receive CIPP lining?

RESPONSE

All new sanitary sewers and lined sanitary sewers are to be CCTV'd internally.

If you have any questions or comments, please feel free to contact me at your earliest convenience. As a reminder, bids will be received until 5:00 p.m. on Monday, March 6, 2023, at the Village of Caldwell's Administrator's Office located at 215 West Street, Caldwell, OH 43724. Good luck to everyone and thank you for your interest in the project.

Sincerely,

THE THRASHER GROUP, INC.





THE INFORMATION CONTAINED HEREIN IS THE SOLE PROPERTY OF THE THRASHER GROUP INC. REPRODUCTION OF THESE DOCUMENTS IN WHOLE OR IN PART, FOR ANY REASON WITHOUT PRIOR WRITTEN PERMISSION, IS STRICTLY PROHIBITED. COPYRIGHT© 2021 THE THRASHER GROUP INC.						SCALE: AS NOTED	<div><div>THRASHER</div><div>400 3rd STREET SE CANTON, OHIO 44702 www.thrashereng.com</div><div>PHONE (330)-451-2042</div><div>FAX (330)-451-2043</div></div>	PHASE No.	VILLAGE OF CALDWELL AREA E, AREA G, AND INTERCETOR 35 PLAN & PROFILE BELFORD ST 0+00-5+00	SHEET No.
						DRAWN: SMD DATE: 23MAR2022				
						CHECKED: ---- DATE: ----		CONTRACT No.		
						APPROVED: ---- DATE: ----				
	2	SMD	29JUL2022	WAS 8" PP, NOW 12" PP		SURVEY DATE:		PROJECT No.		
	1	SMD	29JUL2022	EPA COMMENTS JULY 20, 2022		SURVEY BY:		020-10020		
	No.	BY	DATE	DESCRIPTION		FIELD BOOK No.:				