

**WEST VIRGINIA STATE UNIVERSITY
KANAWHA COUNTY, WEST VIRGINIA
ROOF RENOVATIONS
ADDENDUM #2
July 17, 2024
THRASHER PROJECT #T60-11251
SOLICITATION NUMBER: ARFQ WSC24*06**

TO WHOM IT MAY CONCERN:

A MANDATORY Pre-Bid Conference was held on Tuesday, July 9, 2024, on the above-referenced project. The following are clarifications and responses to questions posed by contractors for the above reference project.

A. GENERAL

1. None

B. SPECIFICATIONS

1. None

C. DRAWINGS

D. QUESTIONS AND RESPONSES

QUESTION

1. Regarding Note #11 – ORD – Could you please confirm that this is to be changed to an overflow drain – appears to be in full use as a roof drain upon field verification?

CONSTRUCTION NOTES

NOTE #	DESCRIPTION
1	PROVIDE NEW EPDM ROOF SYSTEM - REPLACE METAL DECK AS REQUIRED.
2	PROVIDE NEW METAL DRAVEL STOP CONFORMANCE WITH LOCAL CODES.
3	EXISTING ROOF DRAINS TO REMAIN. REPLACE ROOF DRAIN AND STRAINER COVER AS REQUIRED. SEAL ALL GROUND DRAIN, WINDY PANS AND EXISTING ROOF DRAINS TO REMAIN. PROVIDE NEW FLASHING TO RUN UP AND UNDER EXISTING MECHANICAL, WINDY FLASHING SEAL ALL AROUND.
4	REMOVE ROOF ACCESS TO DRAIN.
5	PROVIDE NEW RELIEF PIPE.
6	EXISTING PIPE TO REMAIN. PROVIDE NEW 3/4\"/>

STUDENT UNION ROOF PLAN - PROPOSED
1/8\"/>

RESPONSE

Do not change to overflow drain if field verification confirms a roof drain.

E. CLARIFICATIONS

1. Tapered insulation is not required for entire roof where roof structure provides adequate slope. Use tapered insulation to create crickets at roof penetrations, roof curbs, etc.

If you have any questions or comments, please feel free to contact me at your earliest convenience. As a reminder, bids will be received until **2:30 p.m. on Wednesday, July 24, 2024**. Good luck to everyone and thank you for your interest in the project.

Sincerely,

THE THRASHER GROUP, INC.



AMANDA CHEUVRONT, AIA, NCARB
Project Manager

